

PROJECT COST ESTIMATE

Project No.: 9802

Prepared by: Quynh Hill

Client: Asymchem

Checked by: Chris Dill-Russell

Project Name: Modifications to Existing Footprint

Document No: 9802-RBP-ZZ-ZZ-CP-X-100001

Revision: P01

Document History

Revision No.	Date of Issue	Issued For	Revision Description	Author
P01	15/05/2026	Review	Initial issue	Quynh Hill

ESTIMATE SUMMARY

COST GROUP	DESCRIPTION	COST £K	ACCURACY ±%	COMMENTS
A	EQUIPMENT	1,575	50	SEE EQUIPMENT SHEET
B	CIVILS	326	50	SEE CIVILS SHEET
C	MECHANICAL & PIPEWORK	264	50	SEE M & PW SHEET
D	ELECTRICAL, CONTROL & INSTRUMENTATION	128	50	SEE E I & C SHEET
E	HVAC	35	50	SEE HVAC SHEET
TOTAL DIRECT COSTS		2,329	50	
F	FEED STUDY (±30%)	225	50	FEE ESTIMATE
G	DETAILED DESIGN (±10%)	289	50	FEE ESTIMATE
H	CDM FEES	235	50	ESTIMATED AT 12HR DAYS FOR 1.25 PEOPLE FOR 26 WEEKS INC PC & PD
I	COMMISSIONING	76	50	ESTIMATED AT 12HR DAYS FOR 1 PERSON FOR 12 WEEKS
J	CONTINGENCY	631		20% OF WHOLE PROJECT
CAPEX PROJECT COST		£3,783	50	FEASIBILITY STAGE COST ESTIMATE

EQUIPMENT ESTIMATE

Item No.	Equipment Item	Cost each £K	No. Off	Total Cost £K	Comments
A1 - TANKS/VESSELS					
A1.1	Mobile head tank - 500 litres, SS	35	2	70	Based on similar, recent quote, scaled for size
A1.2	Mobile head tank - 200 litres, SS	30	3	90	Based on similar, recent quote, scaled for size
A1.3	Waste tank - 2000 litres, SS	40	1	40	Based on similar, recent quote, scaled for size
				200	<i>Sub-total A1</i>
A2 - PUMPS					
A2.1	HPLC Transfer pump	10	1	10	Based on similar, recent quote, scaled for size
A2.2	HPLC Waste pump	15	1	15	Based on similar, recent quote, scaled for size
A2.3	Lyophiliser CIP pump	10	1	10	Based on similar, recent quote, scaled for size
A2.4	Lyophiliser CIP waste pump	15	1	15	Based on similar, recent quote, scaled for size
				50.0	<i>Sub-total A3</i>
A3 - EQUIPMENT PACKAGES					
A3.1	HPLC	358	1	358	Hanbon Quote from Asymchem China (air freight)
A3.2	Lyophilizer, Isolator, De-hum and PSG	967	1	967	Quote from Asymchem China including documentation, CE certification, DAP and FAT / commissioning / SAT / IQ / OQ
				1325.0	<i>Sub-total A4</i>
<u>Total New Equipment Purchase Costs in £K</u>				1,575	

CIVIL/STRUCTURAL ESTIMATE

Item No.	Scope of Work	Unit Cost £K	No. off	£K	Comments
B1	Coleman and James (Services)				
	Removal of equipment and plinths, relocating equipment, making good and forming new rooms	271	1	271	Budget quote from supplier based on site visit and scope of works from RB Plant
				271	<i>Subtotal B1</i>
B2	Civils Miscellaneous				
	Civil elements not in Coleman and James' scope	54	1	54	Factored on Coleman and James' costs
				54	<i>Subtotal B2</i>
<u>Total Cost Civils Works in £K</u>				326	

MECHANICAL & PIPING ESTIMATE

Item No.	Scope of Work	Unit Cost £K	No. off	£K	Comments
C1	Install equipment				
	Relocation - Vacuum skid	4	1	4	Site visit, photos
	New Equipment	15	1	15	RBP equipment list & PFD sketches
				19	<i>Subtotal C1</i>
C2	Install instruments				
	Mechanical connections only	1	1	1	PFD Sketches
				1	<i>Subtotal C2</i>
C3	Supply & Install Pipework				
	Disinvestment not in C&J scope	8	1	8	Site visit, P&ID's existing & mark up, photo's, demolition equipment list
	Re-routing as required & supports	11	1	11	Site visit, P&ID's existing & mark up, photo's, demolition equipment list
	Supply and install new pipework & supports	83	1	83	Site visit, new equipment list, PFD sketches
	Fire Protection	50	1	50	Provisional sum
	Access and lifting equipment	24	2	48	For 12 weeks (2 units)
				102	<i>Subtotal C3</i>
C4	Supply & Install Valves & Specials				
				45	Site visit, new equipment list, PFD sketches, hoses (estimate)
				45	<i>Subtotal C4</i>
Total M & PW Costs in £K				264	

ELECTRICAL & INSTRUMENTATION ESTIMATE

Item No.	Scope of Work	unit type	Unit Cost £	No. off	Costs £	Comments
Costs based on SPONS 2026 unless otherwise stated.						
Electrical Power						
D1	Containment - Power					
	Cable Ladder 300mm Heavy DutyGalv	p/m installed	127.83	90	11505	Based on Spons 2026 for main containment runs
	90 deg bends 300mm	per unit installed	73	2	146	Based on Spons 2026 for main containment runs
	Tee 300mm	per unit installed	87	2	174	Based on Spons 2026 for main containment runs
	Allowance for supports @15%				1773.71	
					13598	<i>Subtotal D1</i>
D2	Containment - Controls					
	Cable Ladder 300mm Heavy DutyGalv	p/m installed	127.83	110	14061	Based on Spons 2026 for main containment runs + 20m to access controls room
	90 deg bends 300mm	per unit installed	73	2	146	Based on Spons 2026 for main containment runs
	Tee 300mm	per unit installed	87	2	174	Based on Spons 2026 for main containment runs
	Allowance for supports @15%				2157.2	
					16538	<i>Subtotal D2</i>
D3	Lyophilizer					
	Cable Lyophiliser 35mm ²	p/m installed	44.82	100	4482	
	Termination of cable	Per End	125.94	4	503.76	
	Separate CPC for above 16mm ²	p/m installed	4.21	45	189.45	
	Fuses Lyophiliser 100A	per unit installed	30.78	3	92.34	
					5268	<i>Subtotal D3</i>
D4	HPLC					
	Cable HPLC 4c 10mm ²	p/m installed	23.25	100	2325	
	Termination of cable	Per End	66.84	4	267.36	
	Fuses HPLC 40A	per unit installed	18.94	3	56.82	
					2649	<i>Subtotal D4</i>
D5	Transfer Pump	?	?	?		
	Cable 6mm ² to Transfer Pump	p/m installed	15.91	100	1591	Length allowance
	Termination of cable	Per End	44.83	4	179.32	
	Separate CPC for above	p/m installed	2.53	100	253	Length allowance
	Fuses Transfer pump 25A	per unit installed	10.81	3	32.43	

Item No.	Scope of Work	unit type	Unit Cost £	No. off	Costs £	Comments
					2056	Subtotal D5
D6	Waste Pump					
	Cable 6mm ² to Waste Pump	p/m installed	15.91	100	1591.0	Length allowance
	Termination of cable	Per End	44.83	4	179.3	
	Separate CPC for above	p/m installed	2.53	100	253.0	Length allowance
	Fuses Waste pump 25A	per unit installed	11	3	32	
					2056	Subtotal D6
D7	Lighting & Small Power					
	Atex Light Fixtures	per unit installed	260	12	3120.0	based on Meanwell Explosion Proof Linear LED light 4ft 36W
	Connection of lighting fixtures (LSF Single Core)	per unit installed	250	12	3000.0	SPONS cost x2 factor for ATEX
	Local Isolators (63A)	Unit installed	548.44	4	2193.8	1 per item of equipment 2x factor for ATEX
					8314	Subtotal D7
Controls						
D8	Hardware/Cabling					
	Cable 20pr BS5308 lyophiliser	P/m Installed + Termination	21.46	100	2362.3	Based on Cleveland Cable Quote + Spons rate for installation
	Cable 20pr BS5308 HLPC + mobile tanks	P/m Installed + termination	21.46	100	2362	Based on Cleveland Cable Quote + Spons rate for installation
	Cable 20pr BS5308 Waste Tank	P/m Installed + termination	21.46	120	2792	Based on Cleveland Cable Quote + Spons rate for installation
	Cable 20pr BS5308 1st Floor mobile head tanks	P/m Installed + termination	21.46	100	2362	Based on Cleveland Cable Quote + Spons rate for installation
	Allowance for Final cable to instruments 2pr BS5308	P/m Installed + termination	31.62	800	31312	based on final length of 10m per pair allowed on 20 core
	IJB Lyophiliser	Per box	1200	1	1200	Based on Similar EXe certified JB from previous project
	IJB Waste Tank	Per box	1200	1	1200	Based on Similar EXe certified JB from previous project
	IJB 1st floor Mobile Head Tanks	Per box	1200	1	1200	Based on Similar EXe certified JB from previous project

Item No.	Scope of Work	unit type	Unit Cost £	No. off	Costs £	Comments
	IJB HLPC + Mobile Head Tanks	Per box	1200	1	1200	Based on Similar EXe certified JB from previous project
					45991	Subtotal D8
D9	Instruments					
	Temperature Transmitter (RTD temperature Assembly)	per unit	570	6	3420	Recent Quote from similar project - based on HBS-05-12609 +thermowell stainless steel
	Level Switch	per unit	654	6	3924	Based on Recent Quote from similar project - WIKA Level Switch Tuning Fork 316L
	Level Transmitter	per unit	1223.9	6	7343	Tank Mounted RADAR as per IFM part number LW2120
					14687	Subtotal D9
Day Rate Works						
D10	Day rate works based on work activities that cannot be itemised for example disinvestment activities and commissioning all rates. Based on £500 per day.					
	Testing and Commissioning	Day	600	8	4800	
	Electrical/controls Disinvestment Centrifuge	Day	600	4	2400	
	Electrical Disinvestment Mezzanine support	Day	600	4	2400	
	Relocation Vac Pump	Day	600	3	1800	
	System Integration	Day	600	3	1800	Integration of new signals and logic into Delta V system
	Allowance for labour (30%)				3960	
					17160	Subtotal D10
Total E/I/C Cost in £K					128	

HVAC ESTIMATE

Item No.	Scope of Work	Unit Cost £	No. off	£	Comments
E1	Check existing air volumes	750	1	750	Check air volumes to ensure that correct volumes are currently being
	Inspect existing AHUs serving this area	750	1	750	Prepare report to indicate any issues with existing system
	Site survey and detailed drawings	550	3	1650	Prepare report to indicate any issues
E2	Supply and deliver new ductwork inc. riser extract duct to roof	13000	1	13000	
	Supply and deliver new grilles and volume control dampers	1200	1	1200	
	Thermal insulation	2000	1	2000	
	Dehum discharge duct	1200	1	1200	Plastic duct to prevent corrosion
	Dehum inlet duct	750	1	750	
	Insulate dehum inlet duct	750	1	750	To prevent condensation
E3	Commissioning	750	1	750	
E4	Installation labour	650	10	6500	
E5	HEPA filter move	5000	1	5000	Provisional sum included
E6	O&M manuals/as installed drawings	1000	1	1000	
<u>Total Cost HVAC Works Cost in £K</u>				35.3	