

2.0 SUMMARY

2.0.1 Elemental Cost Plan Summary - Level 1

GIFA 215 m2

Ref	Element		Total £	£/m2
0	Facilitating Works		65,567	305
2	Superstructure		68,690	319
3	Finishes		58,898	274
4	Fittings, Furnishings and Equipment		765,000	3,558
5	Services		537,574	2,500
	Facilitating and Building Works		1,495,729	6,957
9	Preliminaries (incl. Contractor's design)		362,500	1,686
10	Overheads and Profit	5.00%	92,911	432
	Total Building Works Estimate		1,951,140	9,075
11	Professional Services		141,800	660
	SUB-TOTAL		2,092,940	9,735
12	Equipment (supplied by the Client)		1,975,045	9,186
	SUB-TOTAL		4,067,985	18,921
13.1	Design Development Risk (Refer to Risk Register)		397,875	1,851
13.2	Construction Risk		incl above	
	Risk Allowance Estimate		397,875	1,851
	COST LIMIT (excluding inflation)		4,465,860	20,771
14	Inflation	2.15%	96,184	447
	COST LIMIT (including inflation)		4,562,044	21,219
15	VAT	Excluded	-	-
	Total		4,562,044	21,219

Construction Estimate Accuracy	+20%	1,710,000
	-10%	1,280,000
Equipment Estimate Accuracy	+20%	3,280,000
	-10%	2,460,000
Estimate Accuracy	Upper Limit	4,990,000
	Lower Limit	3,740,000

2.0 SUMMARY

2.0.2 Elemental Cost Plan Summary - Level 2

GIFA 215 m2

Ref	Element		Total £	£/m2
0.1	Strip Out, Alterations and Demolition (partitions and the like)		46,967	218
0.2	Strip Out (services)		18,600	87
0	Facilitating Works		65,567	305
2.7	Internal Walls and Partitions		42,440	197
2.8	Internal doors		26,250	122
2	Superstructure		68,690	319
3.1	Wall Finishes		9,810	46
3.2	Floor Finishes		23,631	110
3.3	Ceiling Finishes		25,457	118
3	Finishes		58,898	274
4.1	General fittings, furnishings and equipment		765,000	3,558
4	Fittings, Furnishings and Equipment		765,000	3,558
5.3	Disposal installations		3,000	14
5.4	Water installations		38,600	180
5.6	Heating, Ventilation and Air Conditioning		217,920	1,014
5.8	Electrical installations		107,380	499
5.11	Fire and lightning protection		30,030	140
5.12	Communication, security and control systems		51,345	239
5.13	Special installations		63,700	296
5.14	Builder's Work in Connection with Services		25,599	119
5	Services		537,574	2,500
	Facilitating and Building Works		1,495,729	6,957
9.1	Temporary Works		10,500	49
9.2	Site Welfare and Accommodation		21,000	98
9.3	Design and Construction Management		331,000	1,540
9	Preliminaries (incl. Contractor's design)		362,500	1,686
10	Overheads and Profit	5.00%	92,911	432
	Total Building Works Estimate		1,951,140	9,075
11	Professional Services		141,800	660
	SUB-TOTAL		2,092,940	9,735
12	Equipment (supplied and installed by the Client)		1,975,045	9,186
	SUB-TOTAL		4,067,985	18,921
13.1	Design Development Risk		397,875	1,851
13.2	Construction Risk		incl above	
	Risk Allowance Estimate		397,875	1,851
	COST LIMIT (excluding inflation)		4,465,860	20,771
14	Inflation	2.15%	96,184	447
	COST LIMIT (including inflation)		4,562,044	21,219
15	VAT	Excluded	-	-
	Total		4,562,044	21,219

2.0.2.0 FACILITATING WORKS

Item	Description	Qty	Unit	Rate	Total
1	Strip Out, Alterations and Demolition (partitions and the like)				
	Disconnect and remove antistatic plate adjacent to G128 entrance and set aside for possible re-use by Landlord	1	item	350	350
	General clearance of furniture and laboratory equipment	1	item	7,000	7,000
	Remove floor coverings, skirtings etc and dispose	180	m2	24	4,320
	Remove suspended ceiling and dispose	27	m2	11	297
	Carefully remove existing door between G128 and G128D and set aside for re-use if required	1	item	350	350
	Carefully take down and remove existing blockwork wall between G128 and G128D and dispose	1	item	4,500	4,500
	Form openings through reinforced concrete wall for pass through hatch	2	nr	4,500	9,000
	Form openings through reinforced concrete wall for doorway	2	nr	9,000	18,000
	Carefully remove existing doors between G128B-G128C and G128B-G128A, and set aside in store for re-use by Landlord if required	2	nr	1,200	2,400
	Take out glazed screen and set aside for reuse by Landlord - Proposed doorway to write up area	1	item	750	750
	To Elemental Cost Plan Summary - Level 2				46,967
2	Strip Out (services)				
	Isolate and remove gas pipework / services	1	item	6,000	6,000
	Disconnect and remove ventilation ductwork	1	item	4,000	4,000
	Disconnect and remove electrical installation including light fittings and containment where required	1	item	3,000	3,000
	Isolate from main FA panel, disconnect and remove smoke detectors	1	item	800	800
	Isolate, disconnect and remove Crowcon system	1	item	1,600	1,600
	Isolate, disconnect and remove sink and cupboard from Room 2 and store for re-use / possible relocation to other side of wall later	1	item	600	600
	Isolate, disconnect and remove flow and return pipework, cap off above ceiling level	1	item	600	600
	Isolate, disconnect and remove services from store cupboards	1	item	2,000	2,000
	To Elemental Cost Plan Summary - Level 2				18,600

2.0.2.2 SUPERSTRUCTURE

Item	Description	Qty	Unit	Rate	Total
2.7	Internal Walls and Partitions				
	Wall lining; double skin tape and joint ready for decoration	475	m2	72	34,200
	Infill opening between Rm2 and Rm3 where door removed	3	m2	250	750
	Box in hydrogen pipework in Rm3 (opposite door D3 - Changing room door); extra over item above for wall lining	1	item	850	850
	New partitions; 70mm stud, 2 layers 12.5mm soundblock each side, 25mm APR jointed ready for decoration.	40	m2	166	6,640
To Elemental Cost Plan Summary - Level 2					42,440
2.8	Internal Doors				
	Doorsets; single leaf; semi flush hygienic doors	5	nr	3,250	16,250
	Doorsets; leaf and half; semi flush hygienic doors	1	nr	4,800	4,800
	Doorsets; single leaf; timber to write up space	2	nr	1,800	3,600
	Allow for refurbishing existing doors	4	nr	400	1,600
To Elemental Cost Plan Summary - Level 2					26,250

2.0.2.3 FINISHES

Item	Description	Qty	Unit	Rate	Total
3.1	Wall Finishes				
	Decorate walls to lab	475	m2	18	8,550
	Decorate walls to write up area	70	m2	18	1,260
	To Elemental Cost Plan Summary - Level 2				9,810
3.2	Floor Finishes				
	New sheet vinyl floor to lab	173	m2	111	19,203
	Allow for coved skirting	136	m	18	2,448
	Allow for new carpet in proposed write up area	33	m2	60	1,980
	To Elemental Cost Plan Summary - Level 2				23,631
3.3	Ceiling Finishes				
	New metal suspended ceiling to lab	173	m2	133	23,009
	Allow for perimeter detail (tbc)	136	m	18	2,448
	Assumed ceiling to write up area retained and no works required			-	-
	To Elemental Cost Plan Summary - Level 2				25,457

2.0.2.4 FITTINGS, FURNISHINGS AND EQUIPMENT

Item	Description	Qty	Unit	Rate	Total
	Furniture				
	General allowance for furniture including lockers; step over bench; mobile benches & BIBO bins	1	item	20,000	20,000
	Allow for furniture for write up space	1	item	5,000	5,000
	Equipment				
	Isolators; provisional allowance	4	nr	150,000	600,000
	Isolators; provisional allowance	1	nr	100,000	100,000
	Fume Hoods; assumed existing Fume Hoods are serviceable; provisional allowance made for servicing and repairs if required	1	item	20,000	20,000
	Allow for SF6 Testing	1	item	20,000	20,000
	To Elemental Cost Plan Summary - Level 2				765,000

2.0.2.5 SERVICES

Item	Description	Qty	Unit	Rate	Total
	Disposal installations				
	Allowance for drainage connections (sinks & shower)	1	item	3,000	3,000
	To Elemental Cost Plan Summary - Level 2				3,000
	Water installations				
	Allowance for H&CWS installation (sink and mist shower)	1	item	3,000	3,000
	Take from store and reinstall sink and under cupboard unit	1	item	600	600
	Provisional allowance for mist shower	1	item	35,000	35,000
	To Elemental Cost Plan Summary - Level 2				38,600
	Heating, Ventilation and Air Conditioning				
	Allow for AHU maintenance / bring the system back into use	1	item	20,000	20,000
	Allow for complete ductwork installation to laboratory, including supply air diffusers and extract grilles	182	m2	560	101,920
	Allow for HEPA filters to extract ductwork (Bag in/bag out)	1	item	42,000	42,000
	BMS upgrade; provisional allowance for disconnecting existing BMS controls, provision of new control panel, interfaces with system and commissioning	1	item	50,000	50,000
	Allow for balancing of system	1	item	4,000	4,000
	To Elemental Cost Plan Summary - Level 2				217,920
	Electrical installations				
	Small power installation to lab	182	m2	420	76,440
	Lighting installation to lab	182	m2	170	30,940
	Allow for equipment connections				incl above
	To Elemental Cost Plan Summary - Level 2				107,380
	Fire and lightning protection				
	Allow for installation of sprinkler system to lab	182	m2	165	30,030
	To Elemental Cost Plan Summary - Level 2				30,030
	Communication, security and control systems				
	Access Control to lab entrance door and write up space access	3	nr	3,000	9,000
	Structured cabling installation to lab and write up areas	215	m2	45	9,675
	CCTV to lab and write up areas	215	m2	80	17,200

2.0.2.5 SERVICES

Item	Description	Qty	Unit	Rate	Total
	Fire alarm system to lab	182	m2	85	15,470
	To Elemental Cost Plan Summary - Level 2				51,345
	Special installations				
	Laboratory gas pipework installation	182	m2	350	63,700
	To Elemental Cost Plan Summary - Level 2				63,700
	Builder's Work in Connection with Services				
	Allow for forming holes; fire stopping & access hatches	5%		511,975	25,599
	To Elemental Cost Plan Summary - Level 2				25,599

2.0.2.9 CONTRACTOR'S PRELIMINARIES AND STAFF

Item	Description	Qty	Unit	Rate	Total
	Temporary Works				
	Allow for temporary protection to retained equipment and common areas for the duration of the works	1	item	10,000	10,000
	Allow for temporary lighting	1	item	500	500
	To Elemental Cost Plan Summary - Level 2				10,500
	Site Welfare and Accommodation				
	Welfare and accommodation provided during the construction phase	21	wks	1,000	21,000
	To Elemental Cost Plan Summary - Level 2				21,000
	Design and Construction Management				
	Surveys	1	item	20,000	20,000
	Concept and Co-Ordinated Design [RIBA 2/3] - Contractor's Design including PM and Commercial input	1	item	80,000	80,000
	Detailed Design [RIBA 4] - Contractor's Design including PM and Commercial input	1	item	44,000	44,000
	Construction Stage Resourcing [RIBA 5]				
	People and Expenses	22	wks	8,500	187,000
	To Elemental Cost Plan Summary - Level 2				331,000

2.0.2.11 PROFESSIONAL SERVICES

Item	Description	Qty	Unit	Rate	Total
	Project Management				
	Pre Contract (av 1 day per week)	33	wks	600	19,800
	Post Contract (av 1.5 days per week)	22	wks	900	19,800
	Defects Period	10	Days	600	6,000
	Design Support				
	Pre Contract	1	item	10,000	10,000
	Commercial Support & Contract Administration				
	Pre Contract	1	item	35,000	35,000
	Post Contract	22	wks	2,100	46,200
	Contract close & Final Certificate	1	item	5,000	5,000
	To Elemental Cost Plan Summary - Level 2				141,800

2.0.2.12 EQUIPMENT (SUPPLIED AND INSTALLED BY THE CLIENT)

Item	Description	Qty	Unit	Rate	Total
	Equipment				
	Equipment; refer to Equipment list "Equipment List Costs for scoping 5 Aug"	1	item	1,975,045	1,975,045
	To Elemental Cost Plan Summary - Level 2				1,975,045