



Company	RB Plant Construction Ltd - Lenham, Kent
Designer	Robert Day

Client	Asymchem
Date	15/05/2026

Title	Modifications to Existing Footprint
Project no.	PC9802 -

Document title	MCC-P New Circuit Schedule
----------------	----------------------------

Stage	Concept stage
Status	Preliminary

Circuits schedule report : MCC-P-Utilities and Process MCC		
Company	RB Plant Construction Ltd - Lenham, Kent	
Designer	Robert Day	

Description	Voltage	Phase	From description		
MCC-P-Utilities and Process MCC	400V AC	TP&N	Supply		
Total circuit ways	Spare load	Spare ways	Empty ways		
3Ph: 6 / 1Ph: 18	0%	3Ph: 0 , 1Ph: 0	1Ph: 0 (0%)		
Location:		Mounting:	Surface	Reference No.:	
PFC (kA):	12.03	IP Rating:	IP 4X	Isolator Rating:	
Zs (Ω):	0.0333	Board Rating (A):		Fault Rating (kA):	
Incomer device:				Peak Fault (kA):	23.84

Way	Description	Conductor	Protective devices	In(A)	Ib(A)
1.L1,L2,L3	6/07 - LYO-01-Lyophilizer	4Cx35mm² + 1x16mm² E SWA/XLPE90(70)/Cu,LSZH c-f-2 Length: 100m	Fuse 3P 100A/80kA Generic BS88-2 E (bolted)	100	98.49
2.L1,L2,L3	6/08 - HPLC-Prep HPLC System	4Cx10mm² + 1x4mm² E SWA/XLPE90(70)/Cu,LSZH c-f-3 Length: 100m	Fuse 3P 40A/80kA Generic BS88-2 E (bolted)	40	35.66
3.L1,L2,L3	7/01 - W-PMP-HPLC Waste Pump	3Cx2.5mm² + 1x1.5mm² E SWA/XLPE90(70)/Cu,LSZH c-f-4 Length: 100m	Fuse 3P 25A/80kA Generic BS88-gM A1	25	7.88
4.L1,L2,L3	8/01 - W-PMP02-Lyophilizer Waste Pump 02	3Cx2.5mm² + 1x1.5mm² E SWA/XLPE90(70)/Cu,LSZH c-f-4 Length: 100m	Fuse 3P 25A/80kA Generic BS88-gM A1	25	7.88
5.L1,L2,L3	10/01 - T-PMP-HPLC - Transfer Pump	3Cx2.5mm² + 1x1.5mm² E SWA/XLPE90(70)/Cu,LSZH c-f-5 Length: 100m	Fuse 3P 25A/80kA Generic BS88-gM A1	25	7.88
6.L1,L2,L3	11/01 - CIP-PMP-Lyophilizer CIP Pump	3Cx2.5mm² + 1x1.5mm² E SWA/XLPE90(70)/Cu,LSZH c-f-6 Length: 100m	Fuse 3P 25A/80kA Generic BS88-gM A1	25	7.88