

Equipment List - Removal/Relocation

Project No.: 9802 **Prepared by:** Chris Dill-Russell

Client: Asymchem **Checked by:** Quynh Hill

Project Name: Modifications to existing footprint

Document No: 9802-RBP-ZZ-ZZ-SH-V-320001 **Revision:** P02

Document History

Revision No.	Date of Issue	Issued For	Revision Description	Author
P00	11/03/2026	Review	First issue	Chris Dill-Russell
P01	15/05/2026	Information	Updated following design development	Chris Dill-Russell



EQUIPMENT LIST

Document No. 9802-RBP-ZZ-ZZ-SH-V-320001

Client: Asymchem

Project Title Modifications to existing footprint

Rev.	Equipment No.	Description	Duty/Capacity	Details	Materials of Construction	Supplier/ Model No.	Weight (Kg) (HOLD 1)		Electrical Requirements		PFD No.	Comments
							Empty	Full	Installed Power (kW)	VSD (Y/N)		
PREP HPLC - SUPPLIED BY ASYMCHEM												
		DAC300 Column	300 mm diameter	DAC300 Column	SS	N/A	TBD	-	6	N		Overall system power requirement
		ST50 Slurry tank	100 litres	Glass receiver vessel	SS	N/A	TBD	-	N/A	N/A		
		CP300 pump skid			TBD	N/A	TBD	-	15	N/A		
LYOPHILIZER - SUPPLIED BY ASYMCHEM												
		Freeze dryer chamber					8500	9500	58			Overall system power requirement
		Freeze dryer condenser					2500	4000				
		Refrigeration unit					3000	3500				
		CIP Tank 1	2000 litres				1250	3250				
		CIP Tank 2	2000 litres				1250	3250				
		Isolator					4000	-				
		Dehumidifier					1000	-				
TANKS												
	MHTOX	Mobile head tank	500 litres		SS 316L				N/A	N/A		
	MHTOX	Mobile head tank	500 litres		SS 316L				N/A	N/A		
	MHTOX	Mobile head tank	200 litres		SS 316L				N/A	N/A		
	MHTOX	Mobile head tank	200 litres		SS 316L				N/A	N/A		
	MHTOX	Mobile head tank	200 litres		SS 316L				N/A	N/A		
		Waste tank	2000 litres		SS 316L				N/A	N/A		Located external to building (North Road area)

Rev.	Equipment No.	Description	Duty/Capacity	Details	Materials of Construction	Supplier/ Model No.	Weight (Kg) (HOLD 1)		Electrical Requirements		PFD No.	Comments
							Empty	Full	Installed Power (kW)	VSD (Y/N)		
PUMPS												
		HPLC Transfer pump	3 m³/hr @ 15m TDH		SS 316L					Y		
		HPLC Waste pump	5 m³/hr @ TBD TDH		SS 316L					N		Located near waste tank externally
		Lyophiliser CIP pump	TBD		SS 316L					Y		
		Lyophiliser CIP waste pump	TBD		SS 316L					Y		
Notes: 1. VTA - vendor to advise; VTC - vendor to confirm; TBD - to be determined; N/A - not applicable												
Holds: 1. Equipment weights to be defined/confirmed												